

# **T-217** 1500 HP MOBILE DESERT RIG

# **TECHNICAL OVERVIEW**

Rating **Hook load Drilling depth** theoretical

1.500 HP

1,000,000 lbs @ 12 Lines

16,000 ft

Year of construction 2014

#### **MAST**

Type Kerui, Cantilever for triple with wheels

Height

1,000,000 lbs with 12 lines Hook load

#### **SUBSTRUCTURE**

Type Kerui Self elevating with wheels

Height 30 ft

Casing load 1,000,000 lbs Setback load 500,000 lbs

Type Horsepower rating

Max. Hoisting load

Drilling line diameter

Auxiliary brake

Kerui, E-1500 AC with disc brake

1,500 HP

750.000 lbs with 10 lines

1-3/8"

Dynamic motor brake

# **TOP DRIVE**

Varco TDS 11SA Type

500 Ton Capacity Torque 37,500 ft.lbs

## **ROTARY TABLI**

Type

37-1/2"

Table opening

# **IRON ROUGHNECK**

Type

NOV ST-80

Kerui ZP-375

# **DRIVE GROUP**

Engine type Horsepower Rating Generator type Generator rating Voltage Control Unit

Caterpillar 3512 B (Trailer mounted) 4 x 1436 HP Cat SR4 Brushless

4 x 1,750 KVA 600 V, 60 Hz

**VFD** 



# **MUD SYSTEM**

2 x LS China, Triplex (Trailer mounted) Pump type

2 x 1,600 HP Horsepower rating Standpipe pressure 5,000 psi

Shale shaker 3 No.s

Shale shaker type Derrick flow line

Active mud system 2,000 bbl. Reserve mud syst. 1,000 bbl. Water Tanks 1,000 bbl.

#### BOP EQUIPMENT

Shaffer, 13 <sup>5</sup>/<sub>8</sub>" - 5,000 psi Annular Cameron 13 5/8" - 5000 psi Single ram Cameron 13 5/8" - 5000 psi Double ram

#### CAMP EQUIPMENT

Full rig camp for 140 men

## ADDITIONAL EQUIPMENT

Highly mobile with wheels Anti-Collision System